

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15267-00-00
Spot: N2NENW Sec/Twnshp/Rge: 9-17S-11W
4950 feet from S Section Line, 3300 feet from E Section Line
Lease Name: J F GROSSARDT A Well #: 1
County: BARTON Total Vertical Depth: 3293 feet

Operator License No.: 7757
Op Name: FOLK, MAX LEE DBA FOLK OIL
Address: 604 N. BISMARCK AVE
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3286		125 SX
SURF	10.75	285		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/23/2014 10:00 AM
Plug Co. License No.: 34032 Plug Co. Name: SIEMSEN WELL SERVICE INC.
Proposal Rcvd. from: MAX FOLK Company: FOLK OIL Phone: (620) 252-3300

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/23/2014 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1450', 685' and 240'. Ran tubing to 3083' and pumped 13 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1450' and pumped 125 sx cement w/300 # hulls. Pulled tubing to 250'. Circulated cement to surface on casing w/175 sx cement. Pulled tubing. Circulated cement to surface on surface pipe w/75 sx cement.

GPS: 38.59351 -098.54688

Perfs:

Top	Bot	Thru	Comments
3286	3293		

KCC WICHITA
AUG 07 2014

Remarks: ALLIED CEMENTING TICKET # 55456

RECEIVED

Plugged through: CSG

District: 04

Signed Bruce Rodie
8.12.14 CEM (TECHNICIAN) CM

JUL 29 2014