

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20258-00-01
Spot: N2NENWSE Sec/Twnshp/Rge: 14-34S-31W
2618 feet from S Section Line, 1655 feet from E Section Line
Lease Name: KEATING Well #: 1-14
County: SEWARD Total Vertical Depth: 6055 feet

Operator License No.: 33725
Op Name: FOUNDATION ENERGY MANAGEMEN
Address: 16000 NORTH DALLAS PKWY, STE 875
DALLAS, TX 75248

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3445		WITH 2 SX CMT
PROD	4.5	4300	0	WITH 375 SX CMT
SURF	8.625	1391		WITH 700 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/15/2014 8:00 AM
Plug Co. License No.: 8733 Plug Co. Name: DUNKIN, JERRY, INC.
Proposal Rcvd. from: JOSHUA REHMAN Company: FOUNDATION ENERGY Phone: (918) 845-6884

Proposed Plugging Method: TOP OF FISH @ 3485'. SET CIBP ON FISH WITH 2 SX CMT. PERFORATE AT 1490' WITH 50 SX CMT. PERFORATE AT 600' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/15/2014 4:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 3445' WITH 2 SX CMT. PERFORATE @ 1490' & PUMP 55 SX CMT. TAG CMT AT 1430'. PUMP 25 SX CMT. PERFORATE @ 600' & PUMP 200 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5656	5680		
5630	5638		
5366	5374		
5336	5344		

Remarks: USED COMMON CEMENT BY JERRY DUNKIN.

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 05 2014

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed _____

8.12.14 ckm

(TECHNICIAN)

RECEIVED

JUL 18 2014

KCC DODGE CITY

Form CP-2/3