

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-069-20251-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 16-24S-30W
2985 feet from S Section Line, 2335 feet from E Section Line
Lease Name: GATES Well #: 7-16
County: GRAY Total Vertical Depth: 4995 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4770		WITH 2 SX CMT
DVT		3015		WITH 470 SX CMT
PROD 4.5		4995	0	WITH 150 SX CMT
SURF 8.625		310		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/11/2014 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: CIBP @ 4770' WITH 2 SX CMT. PLUG AT 2000' WITH 25 SX CMT. PLUG AT 1100' WITH 25 SX CMT. PERFORATE 4 HOLES @ 350' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: PARTIAL
Date/Time Plugging Completed: 07/15/2014 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

7/11/14" CIBP @ 4770' WITH 2 SX CMT. PLUG AT 2000' WITH 25 SX CMT. PLUG AT 1100' WITH 25 SX CMT. PERFORATE 4 HOLES AT 350'. CIRCULATE CMT TO SURFACE WITH 125 SX CMT FILLING BOTH THE 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS. CMT FELL BACK. 7/14/14: RUN TBG & TAG TOC IN 4 1/2" CASING AT 1543'. PUMP THRU PERFS @ 350' @ 1 BPM @ 390#. NO BLOW OR CIRCULATION UP 4 1/2" X 8 5/8". LOAD 4 1/2" X 8 5/8" ANNULUS WITH 16 BBL WATER & PRESSURE UP. COULD NOT CIRCULATE. RUN CBL. TAG SOFT CMT AT 1272' IN 4 1/2". FOUND CMT @ 296' TO 380'. BOTTOM OF SURFACE CASING IS ISOLATED. PERFORATE AT 210'. RUN TBG TO 1100'. 7/15/14: CIRCULATE CMT TO SURFACE UP THE 2 3/8" X 4 1/2" ANNULUS AND THE 4 1/2" X 8 5/8" ANNULUS LEAVING BOTH FULL OF CMT USING 110 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4826	4828		

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 05 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Ken Jehlik
8.6.14 CKM (TECHNICIAN)

RECEIVED

JUL 28 2014

KCC DODGE CITY