

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21792-00-00
Spot: E2W2SWNE Sec/Twnshp/Rge: 3-16S-18W
1980 feet from N Section Line, 2230 feet from E Section Line
Lease Name: MORRIS HERL Well #: 1
County: RUSH Total Vertical Depth: 3610 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3160		WITH 2 SX CMT
CIBP		3480		
PROD	4.5	3587	1680	WITH 225 SX CMT
SURF	8.625	1130		WITH 450 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/02/2014 4:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Revd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: SET CIBP @ 3160' WITH 2 SX CMT. PLUG AT 1160' WITH 15 SX GEL & 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE
Date/Time Plugging Completed: 07/02/2014 5:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

CIBP @ 3160' WITH 2 SX CMT. 1ST PLUG AT 1155' WITH 15 SX GEL & 50 SX CMT.
2ND PLUG AT 557' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3489	3493		
3438	3503		
3232	3235		
3209	3437		
2926	2930		
2349	3253		

KCC WICHITA
JUL 24 2014
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed

8.6.14 CKM

(TECHNICIAN)

RECEIVED

JUL 17 2014

KCC DODGE CITY

Form CP-2/3