

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-171-21080-00-00  
Spot: SENWNWNE Sec/Twnshp/Rge: 19-16S-33W  
360 feet from N Section Line, 2050 feet from E Section Line  
Lease Name: LYNX Well #: 1  
County: SCOTT Total Vertical Depth: 4800 feet

Operator License No.: 9860  
Op Name: CASTLE RESOURCES, INC.  
Address: BOX 87  
SCHOENCHEN, KS 67667

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	303		WITH 190 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/08/2014 12:30 AM  
Plug Co. License No.: 34743 Plug Co. Name: WHITE KNIGHT DRILLING LLC  
Proposal Rcvd. from: TERRY AUSTIN Company: WHITE KNIGHT DRILLING LLC Phone: (785) 625-5155

Proposed Plugging Method: 1ST PLUG AT 2460' WITH 50 SX CMT. 2ND PLUG AT 1650' WITH 80 SX CMT. 3RD PLUG AT 840' WITH 50 SX CMT. 4TH PLUG AT 330' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE  
Date/Time Plugging Completed: 07/08/2014 2:30 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

1ST PLUG AT 2460' WITH 50 SX CMT. 2ND PLUG AT 1650' WITH 80 SX CMT. 3RD PLUG AT 840' WITH 50 SX CMT. 4TH PLUG AT 330' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed [Signature]  
8-6-14 CKM (TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 05 2014

CONSERVATION DIVISION  
WICHITA, KS

RECEIVED

JUL 18 2014

KCC DODGE CITY

Form CP-2/3