

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20993-00-00
Spot: NESWSW Sec/Twnshp/Rge: 11-25S-32W
990 feet from S Section Line, 4290 feet from E Section Line
Lease Name: HICKS Well #: 2-11
County: FINNEY Total Vertical Depth: 5130 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3068	0	WITH 380 SX CMT
SURF	8.625	1939		WUTG 1050 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/01/2014 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: BUD NEFF Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PLUGGING PROPOSAL AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/01/2014 12:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

PUMP 100 SX CMT WITH 300# HULLS DOWN 4 1/2" CASING. DISPLACE WATER TO 1000' & TEST CASING TO 700#. RUN CBL DETERMINE TOC BELOW USABLE WATER. PERFORATED AT 910' & PUMPED 190 SX CMT CIRCULATE TO 0'.

Top	Bot	Thru	Comments
2554	2591		

KCC WICHITA
JUL 24 2014
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed _____

(TECHNICIAN)

8-6-14 CEM

RECEIVED

JUL 17 2014

KCC DODGE CITY

Form CP-2/3