

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20102-00-00
Spot: SWNE Sec/Twnshp/Rge: 17-21S-40W
3284 feet from S Section Line, 1949 feet from E Section Line
Lease Name: GRILLIOT Well #: 1-17
County: HAMILTON Total Vertical Depth: 2840 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1190		
PROD	4.5	2836	0	WITH 150 SX CMT
SURF	8.625	258		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/08/2014 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (405) 935-7987

Proposed Plugging Method: PUMP 100 SX CMT WITH 200# HULLS. DISPLACE WITH WATER TO 1200'. TEST CASING TO 700#. RUN CBL TO FIND TOC. PERFORATE & OR RUN TBG AS NECESSARY.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/08/2014 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 100 SX CMT WITH 200# HULLS DOWN 4 1/2" CASING. DISPLACE TO 1450' & PRESSURE TO 600#. PRESSURE KEEPS BLEEDING OFF TO VACUUM RAPIDLY. RUN CBL FROM 1190' TO 175'. TOC AT 800'. SET CIBP @ 1190'. FLUID LEVEL AT 185'. PERFORATE 4 HOLES AT 390'. RUN TBG TO 1150' & CIRCULATE CMT UP 4 1/2" ANNULUS TO SURFACE WITH 120 SX CMT. TOOH WITH TBG. PUMP CMT DOWN 4 1/2" CASING OUT PERFS & CIRCULATE CMT TO SURFACE UP THE 4 1/2" X 8 5/8" ANNULUS WITH 70 SX CMT, LEAVING THE CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2766	2778		


RECEIVED
KANSAS CORPORATION COMMISSION
AUG 05 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

8.6.14 CKM

RECEIVED

JUL 18 2014

KCC DODGE CITY

Form CP-2/3