

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20203-00-00
Spot: NWNWNWSE Sec/Twnshp/Rge: 13-21S-40W
2590 feet from S Section Line, 2590 feet from E Section Line
Lease Name: THIESSEN Well #: 2-13
County: HAMILTON Total Vertical Depth: 2820 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2820	0	WITH 500 SX CMT
SURF	8.625	379		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/17/2014 2:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 100 SX CMT WITH 200# HULLS. DISPLACE WITH WATER TO 1200'. TEST CASING TO 700#. PERFORATE AND/OR RUN TBG AS NECESSARY.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/17/2014 6:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 100 SX CMT WITH 200# HULLS DOWN 4 1/2" CASING. DISPLACE WITH WATER TO 1260'. TEST CASING TO 500#. HOLE IN CASING 5' BGL. RUN CBL FROM 1300' TO 88'. TOC @ 366'. CONTAMINATED CMT TO 285'. PERFORATE 4 HOLES AT 270'. RUN TBG TO 1197'. CIRCULATE CMT TO SURFACE UP THE 4 1/2" CASING WITH 80 SX CMT. NO CIRCULATION UP THE 4 1/2" X 8 5/8" ANNULUS. TOOH W/TBG. HOOK UP TO THE 4 1/2" CASING. TOP OFF WITH 10 SX CMT & ATTEMPT TO PUMP INTO PERFS AT 270'. COULD NOT. HOOK UP TO 4 1/2" X 8 5/8" ANNULUS & PUMP 5 SX CMT & WELL PRESSURED UP. COULD NOT CIRCULATE.

Perfs:

Top	Bot	Thru	Comments
2763	2770		


RECEIVED
KANSAS CORPORATION COMMISSION
AUG 05 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

8-6-14 CKM

RECEIVED

JUL 28 2014

KCC DODGE CITY

Form CP-2/3