

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20374-00-00
Spot: SWSW Sec/Twnshp/Rge: 2-23S-40W
660 feet from S Section Line, 660 feet from W Section Line
Lease Name: BRADDOCK Well #: 1-2
County: HAMILTON Total Vertical Depth: 2650 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2649	0	WITH 500 SX CMT
SURF	8.625	346		WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/17/2014 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 100 SX CMT & 200# HULLS. DISPLACE WITH WATER TO 1100'. TEST CASING TO 700#. RUN CBL TO DETERMINE TOC. PERFORATE AND/OR RUN TBG AS NECESSARY.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/17/2014 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 100 SX CMT WITH 200# HULLS DOWN 4 1/2" CASING. DISPLACE WITH WATER TO 1100'. PRESSURE UP & TEST CASING TO 700#. HOLDING. RUN CBL FROM 1180' TO 25'. TOC @ 105'. RUN TBG TO 1119'. CIRCULATE CMT TO SURFACE UP 4 1/2" CASING USING 85 SX CMT. TOOH WITH TBG & TOP OFF WITH 15 SX CMT. PUMP 10 SX CMT DOWN THE ANNULUS TO 300#.

Perfs:

Top	Bot	Thru	Comments
2585	2594		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG


RECEIVED
KANSAS CORPORATION COMMISSION

AUG 05 2014

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed _____



(TECHNICIAN)

8.6.14 ckm

RECEIVED
JUL 28 2014
KCC DODGE CITY

Form CP-2/3

