

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-075-20386-00-00  
Spot: SWSW Sec/Twnshp/Rge: 1-23S-40W  
660 feet from S Section Line, 660 feet from W Section Line  
Lease Name: O BRATE Well #: 1-1  
County: HAMILTON Total Vertical Depth: 2675 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2675	0	
SURF	8.625	367		WITH 275 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/08/2014 2:30 PM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 250# HULLS & 90 SX CMT. DISPLACE TO 1200' & TEST CASING TO 700'. RUN CBL TO DETERMINE TOC. PERFORATE AND/OR RUN TBG AS REQUIRED.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/08/2014 5:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 100 SX CMT WITH 250# HULLS DOWN 4 1/2" CASING. DISPLACE WITH WATER TO 1400'. TEST CASING TO 700#. HOLDING. RUN CBL FROM 1199' TO 20'. TOC @ 70' FROM SURFACE. RUN TBG TO 1117' & CIRCULATE CMT UP 2 3/8" X 4 1/2" ANNULUS TO SURFACE WITH 85 SX CMT. TOOH WITH TBG. TOP OFF 4 1/2" CASING WITH 25 SX CMT. PUMP 6 SX CMT DOWN THE ANNULUS TO 300#.

Perfs:

Top	Bot	Thru	Comments
2631	2642		

RECEIVED  
KANSAS CORPORATION COMMISSION  
**AUG 05 2014**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed *Ken Jehlik*  
8-6-14 scm (TECHNICIAN)

RECEIVED  
JUL 18 2014  
KCC DODGE CITY

Form CP-2/3