

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-075-20489-00-00  
Spot: SESE Sec/Twnshp/Rge: 20-21S-40W  
691 feet from S Section Line, 655 feet from E Section Line  
Lease Name: BOGNER Well #: 2-20  
County: HAMILTON Total Vertical Depth: 5450 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2090		WITH 2 SX CMT
PROD	4.5	2947	0	WITH 960 SX CMT
SURF	8.625	1368		WITH 600 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/09/2017 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 110 SX CMT WITH 150# HULLS DOWN CASING. DISPLACE WITH WATER TO 1200'. RUN BOND LOG FROM 1200' TO TOC. RUN TBG AND OR PERFORATE AS REQUIRED.

Plugging Proposal Received By: KEN JEHLIK WitnessType: PARTIAL  
Date/Time Plugging Completed: 07/10/2014 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

7/9/14: TBG STUCK IN HOLE. SHOT OFF AT 2504'. WOULD NOT COME. SHOOT OFF AT 2100'. CAME FREE. TOOH. SET CIBP @ 2090' WITH 2 SX CMT. LOAD HOLE & PRESSURE TO 500#. SLIGHT BLEED OFF. RUN CBL. FLUID IN WELL TOO FOAMY. RUN TBG TO 2000' & CIRCULATE OUT FOAM. RERUN CBL FROM 1200' TO SURFACE. TOC @ SURFACE. 7/10/14: RUN TBG TO 1200'. CIRCULATE CMT TO SURFACE UP 2 3/8" X 4 1/2" ANNULUS WITH 95 SX CMT. TOP OFF WITH 15 SX CMT. 5 SX CMT DOWN TO ANNULUS TO 300#.

Perfs:

Top	Bot	Thru	Comments
2772	2777		

RECEIVED  
KANSAS CORPORATION COMMISSION  
**AUG 05 2014**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

RECEIVED  
JUL 17 2014  
KCC DODGE CITY

Signed

*Ken Jehlik*  
8.6.14 CKM

(TECHNICIAN)

Form CP-2/3