

To: 1 051678 6-18
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20,154 20546-0000
C SW NE, SEC. 11, T. 34 S, R. 20 W/EX
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30972
Operator: Bishop Operating Co. Inc.
Name:
Address P.O. Box 1807
Hutchinson, KS 67504

Lease Name Christion Well # 2-11
County Comanche
Well Total Depth 4830 156.97 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 672

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 1:30 p.m. Day: 18 Month: 6 Year: 19 93

Plugging proposal received from Jeff Sletto
(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4820' w/150 sx cement, PBTD 4758', Perfs at 4700-45'
1st plug sand back to 4650' and dump 5 sx cement on top of sand through bailer,
2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:15 p.m. Day: 18 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4650' and dumped 5 sx cement on top of sand
through bailer,
2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, released 8 5/8" wiper plug and pumped 125 sx cement.
Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3500' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
(if applicable) observe this plugging.

DATE 6-24-93
INV. NO. 37995

Signed Richard W. Lucas
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMM
JUN 23 1993
06-23-93
CONSERVATION DIVISION
Wichita, Kansas