

1 080275

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NW NW _____, SEC. 25, T 34 S, R 20 (1W) EX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,502-0000
4620 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6420

Lease Name Water Well # 1-25
County Comanche 141.05
Well Total Depth 4340 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 615

Operator: K.R.M. Petroleum Corp.
Name & Address 1900 Grant Street, Suite 300
Denver, CO 80203

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:00 am Day: 5 Month: December Year: 19 84

Plugging proposal received from Norman Voth
(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 5235' PBD 5303' Perfs at 4804-10'
1st plug pump 45 sx cement to bottom and set plug at 4403'
2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 125 sx cement

RECEIVED
STATE CORPORATION COMMISSION
DEC 12 1984
12-12-84
CONSERVATION DIVISION
WICHITA, KANSAS
(TECHNICIAN)

Plugging Proposal Received by J. H. [Signature]

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 12:00 pm Day: 5 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 5235' PBD 5303' Perfs at 4804-10'
1st plug pumped 45 sx cement to bottom and set plug at 4403', 2nd plug squeezed well with
3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber
plug and pumped an additional 125 sx cement.

Maximum pressure 500 psi and shut in 3-0 psi

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun. Recovered 3980' 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 12-20-84
INV. NO. 6072

Signed [Signature] (TECHNICIAN) SR