

1091069

TO: STATE CORPORATION COMMISSION

API NUMBER 15-033-20,251-0000  
NE/4 SEC. 29, T 34 S, R 20 W

CONSERVATION DIVISION - PLUGGING SECTION 215 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1105 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME WOOLFOLK E WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY COMANCHE

OPERATOR LICENSE # 5399 8/17

WELL TOTAL DEPTH 5550 180.38 FEET

OPERATOR: AMERICAN ENERGIES CORPORATION PRODUCTION CSG: SIZE 4 1/2" @ 5549' WITH 150 SX

NAME AND ADDRESS 155 N MARKET #710 SURFACE CASING: SIZE 8 5/8" @ 714' WITH 600 SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DS&W WELL SERVICING LICENSE NUMBER 6901

ADDRESS PO BOX 231 CLAFLIN, KS 67525

COMPANY TO PLUG AT: HOUR: 12:15 PM DAY: 17 MONTH: 08 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) DS&W (PHONE) 316-587-3361

WERE: PERFS AT 5420-23

CIBP AT 5370' WITH 2 SX CEMENT ON TOP. PUMP DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX

CEMENT - 10 SX GEL - 100# HULLS - 150 SX CEMENT. PUMP PRESSURE 500#. SHUT IN WITH 500#.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:15 PM DAY: 17 MONTH: 08 YEAR: 2000

ACTUAL PLUGGING REPORT

CIBP AT 5370' WITH 2 SX CEMENT ON TOP. PUMP DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX

CEMENT - 10 SX GEL - 100# HULLS - 150 SX CEMENT. PUMP PRESSURE 500#. SHUT IN WITH 500#.

RECEIVED  
STATE CORPORATION COMMISSION  
8-22-00  
AUG 22 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 4140' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)

I (DID) OBSERVE THIS PLUGGING

INVOICED

SIGNED

DATE

8/24/00

(TECHNICIAN)

FORM CP-2/3

INV. NO.

2001060514

CONSERVATION DIVISION  
Wichita, Kansas  
2