

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-20421-00-00
Spot: N2NESW Sec/Twnshp/Rge: 6-35S-11W
2310 feet from S Section Line, 3300 feet from E Section Line
Lease Name: RATHGEBER Well #: A-2
County: BARBER Total Vertical Depth: 5170 feet

Operator License No.: 33235
Op Name: CHIEFTAIN OIL CO., INC.
Address: 101 S. 5TH ST. PO BOX 124
KIOWA, KS 67070

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4740		WITH 2 SX CMT
PROD	4.5	5169	2700	WITH 250 SX CMT
SURF	8.625	908		WITH 450 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 07/15/2014 8:30 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4740' WITH 2 SX CMT. PLUG AT 950' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 07/15/2014 10:15 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SET CIBP @ 4740' WITH 2 SX CMT. 1ST PLUG AT 976' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 406' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4794	4804		

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 05 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed

Ken Jehlik
8.8.14 ckm

(TECHNICIAN)

RECEIVED

JUL 18 2014

KCC DODGE CITY

Form CP-2/3