

4-020143

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-009-20,650 - 00.00

SE NE NW /4 SEC. 33, 16 S, 11 W  
4290 feet from S section line  
2970 feet from E section line

Operator license# 5363

Lease: Harzman Well # 1

Operator: Berexco, Inc.

County: Barton

Address: P.O. Box 723  
Hays, Kansas 67601

Well total depth 3416 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 250 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Western Well Service License# 32128

Address: P.O. Box 680 - Hays, Kansas 67601

Company to plug at: Hour: 10:00 A.M. Day: 6 Month: July Year: 2000

Plugging proposal received from: Dennis Kirmer

Company: Berexco, Inc. Phone: 785-628-6101

Were: Ordered out 300 sxs 60/40 pozmix - 10% gel - 600# hulls.  
Cast iron bridge plug at 3140'.  
Prod. Perfs at 2306' - 2308'; 2518' - 2520' - 3067' - 3068'; 3104' - 3106';  
3160' - 3161'; 3357' - 3359'; 3358' - 3360'.  
Fluid level at 1300'.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 11 2000

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All , Part , None

CONSERVATION DIVISION  
Wichita, Kansas

Completed: Hour: 2:00 P.M., Day: 6 Month: July Year: 2000

Actual plugging report: 8 5/8" set at 250' w/175 sxs. 5 1/2" set at 3416' w/150 sxs.  
Perforated casing at 1475' - 790' - 475'.  
Ran tubing to 2015' - tied onto and spotted 180 sxs with 400# hulls.  
Pulled tubing to 1023' - tied onto and circulated with 80 sxs with 200# hulls.  
Pulled tubing out of the hole.  
Tied onto 5 1/4" casing and squeezed with 25 sxs. Max. P.S.I. 600#. S.I.P. 400#.  
Tied onto casing annulus and squeezed with 15 sxs. Max. P.S.I. 500#. S.I.P. 200#.

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO   
Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO   
Plugged through TUBING , CASING  Elevation: 1818 GL

I did  / did not  observe the plugging.

*Gay Pfeiffer*  
(agent)

INVOICED  
DATE 7/13/00  
WELL NO. 1060053

Form CP-2/3

*(Handwritten signature)*