

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23435-00-00

Spot: SWSNWSE

Sec/Twnshp/Rge: 32-16S-11W

1450 feet from S Section Line, 1850 feet from E Section Line

Lease/Unit Name: BRINSON

Well Number: 2

County: BARTON

Total Vertical Depth: 3372 feet

Operator License No.: 8653

Conductor Pipe: Size

feet:

Operator Name: PETROLEUM TECHNOLOGIES, IN

Surface Casing: Size 8.62

feet: 362

225 SX CMT

Address: 801 W. 47TH ST STE 412

Production: Size 5.5

feet: 3371

150 SX CMT

KANSAS CITY, MO 64112

Liner: Size

feet:

109.59

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/24/2000 12:00 PM

Plug Co. License No.: 6901

Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: BRIAN

Company: D S & W WELL SERVICING, INC.

Phone: (816) 587-3361

Proposed
Plugging
Method:

Plugging Proposal Received By: HUBERT DEINES

WitnessType: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 11/24/2000 1:30 PM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 3250' and dumped 5 sxs cement.

Cut off pipe at 1580'.

Pulled to 1500' and pumped 110 sxs 60/40 pozmix - 10% gel cement.

Pulled to 850' and pumped 40 sxs cement.

Pulled to 300' and circulated with 90 sxs cement.

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 01 2000
CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: CSG

District: 04

Signed

Case Morris

(TECHNICIAN)

INVOICED

DATE

12/1/00

NOV. 29


2001061045

Form CP-2/3

NOV 29 2000

W0000003 809

PETROLEUM ENERGY, INC.
 415 1ST NATL BK BLDG. #2 BRINSON 32-16-11W
 WICHITA, KS 67202 1450' FSL&
 1850' FEL, SE/4
 CONTR WHITE & ELLIS DRILLING CTY BARTON
 GEOL FIELD KRAFT-PRUSA
 ELV 1891 KB SPD 2/2/84 CARD ISSUED 3/1/84 IP P 31 BOPD, NW
 1886 GL ARB 3322-3326



SMP	Tops	Depth/Datum
HEEB		2940-1049
TOR		2957-1066
DOUG		2969-1078
BR LM		3037-1146
LANS		3053-1162
BKC		3293-1402
ARB		3319-1428
RTD		3372-1481

API 15-009-23,435
 8 5/8 " 362/225 SX; 5 1/2 " 3371/150 SX
 DST (1) 2965-3006 (DOUG SD) / 30-30-30-30, REC 60' OCM, SIP
 741-536#, FP 37-47 / 50-62#
 DST (2) 3285-3333 (ARB) / 30-30-30-30, REC 1600' OIL, NW,
 SIP 1079-1079#, FP 112-387 / 450-584#
 MICT - CD, PF (ARB) 3322-26, SWB 7.12 BOPD, NW, NAT, POP,
 P 31 BOPD, NW, 2/20/84