

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23875-00-00
Spot: CS2SWSE , Sec/Twnshp/Rge: 32-16S-11W
330 feet from N Section Line, 1980 feet from W Section Line
Lease/Unit Name: BRINSON Well Number: 3
County: BARTON Total Vertical Depth: 3367 feet

Operator License No.: 8653
Op Name: PETROLEUM TECHNOLOGIES, INC.
Address: 801 W. 47TH ST STE 412
KANSAS CITY, MO 64112

Conductor Pipe: Size feet:
Surface Casing: Size 8.62 feet: 358 210 SX CMT \$109.43
Production: Size 5.5 feet: 3366 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/09/2001 11:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: MIKE KELSO Company: D S & W WELL SERVICING, INC. Phone: (316) 587-3361

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 10% gel - 500# hulls.
Perfs 3332' - 3335'.
Sand. Shoot casing.
1425' - 100 sxs with 300# hulls.
775' - 40 sxs with 100# hulls.
250' - 45 sxs.
Top - 20 sxs.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/09/2001 1:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Sanded to 3270' and spotted 5 sxs cement with dump bailer.
Shot casing at 1954'.
Pulled casing to 1450' - pumped 80 sxs 60/40 pozmix with 300# hulls -
cement started circulating from casing leaks.
First casing leak was 246' - 820' - 1107' - 1558'. Pulled casing from hole.
Tied onto 8 5/8" with swedge and pumped 80 sxs with 200# hulls
with Max. P.S.I. 700#. S.I.P. 500#.

Remarks: ALLIED CEMENTING COMPANY - TICKET #8569.

Plugged through: CSG

District: 04

Signed *Patricia Staab*
(TECHNICIAN)

RECEIVED

NOV 14 2001

KCC WICHITA

INVOICED

DATE 11-14-01


INV. NO. 2002060943

NOV 13 2001

PETROLEUM ENERGY, INC. 32-16-11W
 224 E. DOUGLAS, #350 #3 BRINSON C S/2 SW SE
 WICHITA, KS 67202
 CONTR. WHITE & ELLIS DRILLING CTY BARTON

GEOLOGICAL FIELD KRAFT-PRUSA

ELV 1887 KB SPD 2/5/85 CARD ISSUED 3/28/85 IP P 40 BOPD & WTR
1882 GL DRLG COMP 3/11/85 ARB 3332-3335



SMP	Tops	Depth/Datum	API 15-009-23,875
			8 5/8 " 358 / 210SX, 5 1/2 " 3366 / 150SX
HEEB		2935-1048	DST (1) 2961-3000 (DOUG) / 45-45-45-45, FB, REC 70' SLI
TOP		2951-1064	OCM, SIP 925-883#, FP 41-41 / 52-52#
DOUG		2963-1076	DST (2) 3290-3327 (LKC) / 30-30-30-30, SB, REC 225' OCM, SIP
BR LM		3030-1143	1070-1070#, FP 52-83 / 93-104#
LANS		3046-1159	MICT - CO, PF (ARB) 3332-3335, BAILED 10 GFPH (77% OIL),
ARB		3315-1428	SWB 9.6 BOPH PLUS WTR, POP, P 40 BOPD & WTR.
RTD		3367-1480	