

4-020108

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-23,907 . 00 . 00

C N2 NW /4 SEC. 18 , 16 S, 11 W
4620 feet from S section line
3960 feet from E section line

Operator license# 6357

Lease: Krier Well # A-3

Operator: Webco Oil Company, Inc.

County: Barton 112.13

Address: 1303 Baker Avenue 2/16
Great Bend, Kansas 67530

Well total depth 3450 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 336 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Quality Well Service License# 31925

Address: 249 E. Beth Drive - Sterling, Kansas 67579

Company to plug at: Hour: 9:30 A.M. Day: 16 Month: February Year: 2000

Plugging proposal received from: Richard McIntyre

Company: Quality Well Service Phone: 316-278-2476

Were: Ordered out 200 sxs 60/40 pozmix - 10% gel - 400# hulls.
Prod Perfs at 2863' - 2868'; 3120' - 3123'; 3205' - 3208'; 3059' - 3062';
3191' - 3194'; 3311' - 3313'.
Cut casing off at 1820'.
PBTD 3250'.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All , Part , None

Completed: Hour: 12:00 P.M. , Day: 16 Month: February , Year: 2000

Actual plugging report: 8 5/8" set at 336' w/185 sxs. 5 1/2" set at 3368' w/225 sxs cmt.
Sanded back to 2776' and topped with 5 sxs cement with dump bailer.
Cut casing off at 1820'.

Pulled casing to 1400' - tied onto and pumped 100 sxs cement with 300# hulls.
Pulled casing to 750' - tied onto and spotted 50 sxs cement with 100# hulls.
Pulled casing to 200' - tied onto and circulated cement with 50 sxs.
Pulled casing out of hole.
Hole standing full of cement.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD
Bottom plug(in place): YES , CALC , NO
Plugged through TUBING , CASING .
Anhy.plug: YES NO
Dakota plug: YES , NO
Elevation: 1872 GL

I did / did not observe the plugging.

INVOICED 10.
DATE 2/28/00
INV. NO. 061320

RECEIVED
STATE CORPORATION COMMISSION
(agent)
FEB 22 2000 Form CP-2/3

CONSERVATION DIVISION
Wichita, Kansas