

To: 1 051681
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-18 API NUMBER 15- 033-20,543-0000
C NE NW, SEC. 11, T. 34 S, R. 20 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 30972
Operator: Bishop Operating Company Inc.
Name & Address: P.O. Box 1807
Hutchinson, KS 67504

4620 feet from S section line
3300 feet from E section line
Lease Name Beyler Well # 2-11
County Comanche
Well Total Depth 4835 157.13 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 655

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 11:50 a.m. Day: 18 Month: 6 Year: 19 93

Plugging proposal received from Jeff Sletto
(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4835' w/200 sx cement, PBTD 4784', Perfs at 4755-59'
1st plug sand back to 4700' and dump 5 sx cement on top of sand through bailer,
2nd plug pump down 8 5/8" with 300 lbs.hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:50 p.m. Day: 18 Month: 6 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3500' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 6-24-93
37994

Signed Richard M. Lacy (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JUN 23 1993
6-23-93
CONSERVATION DIVISION
Wichita, Kansas