

To: 1 051674 6-14  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-033-20,536 - 0000  
C NW SE, SEC. 11, T. 34 S, R. 20 W/E  
1980 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30972  
Operator: Bishop Operating Company, Inc.  
Name & Address: P.O. Box 1807  
Hutchinson, KS 67504

Lease Name Petro 11 Well #3  
County Comanche  
Well Total Depth 4850 157.62 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 590

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105  
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9 a.m. Day: 14 Month: 6 Year: 19 93

Plugging proposal received from Jeff Sletto  
(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4838' w/200 sx cement, Perfs at 4744-54'  
1st plug sand back to 4690' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.  
hulls and 125 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:50 a.m. Day: 14 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4690' and dumped 5 sx cement on top of sand through bailer,  
2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.  
hulls, and 125 sx cement.

Maximum pressure 600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3550' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
observe this plugging.

DATE 6-24-93  
INV. NO. 37986

Signed Richard W. Lucas (TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 18 1993  
6-18-93  
CONSERVATION DIVISION  
Wichita, Kansas