

No. 1 090273
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-23

API NUMBER 15-033-20,521-0000 94R
C NW NE, SEC. 11, T 34 S, R 20 W/E
4620 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30972
Operator: Bishop Operating Company, Inc.
Name & Address: P.O. Box 1807
Hutchinson, KS 67504

Lease Name Christian Well # 1-11
County Comanche 156.65
Well Total Depth 4820 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 615

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 10 a.m. Day: 23 Month: 4 Year: 19 93

Plugging proposal received from Vernon Duntz
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

work: 5 1/2" at 4809' w/200 sx cement, Perfs at 4749-53'
1st plug sand back to 4700' and dump 5 sx cement on top of sand through bailer,
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 11 a.m. Day: 23 Month: 4 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 5 sx cement on top of sand through bailer,
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"
wiper plug and pumped 150 sx cement.
Maximum pressure 500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3700' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
APR 28 1993
CONSERVATION DIVISION
Wichita, Kansas

observe this plugging.

Signed [Signature] (TECHNICIAN)

INVOICED
DATE 5-11-93
INV. NO. 37661

15-033-20521-0000

K.R.M. PETROLEUM CORP
 820 GUARANTY BK BLDG #1-11 CHRISTIAN 11-34-20W
 DENVER, CO 80202 C NW NE
 CONTR ALDEBARAN DR LG CO CTY COMANCHE

GEOL _____ FIELD LEMON RANCH EXT (1/8 E)

E 1793 KB CM 12/17/81 CARD ISSUED 5/20/82 IP SIGW

		*
+		+
+		+

API 15-033-20,521

SWOPE 4749-4753

LOG TOPS	DEPTH	DATUM
HEEB	4144	-2351
DOUG	4172	-2379
LANS	4334	-2541
IOLA	4580	-2787
STARK	4730	-2937
SWOPE	4748	-2955
HUSH	4784	-2991
TD	4820	-3027

8-5/8" 615/650sx, 5 1/2" 4809/200sx

DST (1) 4752-4770/25-30-30-30, 1ST OP
 FLO 2740 MCFG, 2ND OP 2630 MCFG,
 REC 10' COND & 60' MCO, SIP 1743-
 1733#, FP 487-468/454-453#, HP
 2379-2283#

MICT - CO, PF 8/4749-4753, AC 2500G,
 KO FLO, SI

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

APR 2 1993
 4-2-93
 CONSERVATION DIVISION
 WICHITA, KANSAS

RECEIVED
 STATE CORPORATION COMMISSION