

To: 1 051673  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

6-15 API NUMBER 15- 033-20,486 - 0000  
C SE SE , SEC. 11 , T. 34 S, R 20 W/E  
660 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30972  
Operator: Bishop Operating Company Inc.  
Name & Address P.O. Box 1807  
Hutchinson, KS 67504

Lease Name Petro 11 Well # 2  
County Comanche  
Well Total Depth 4900 159.25 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 669

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A   
Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105  
Address P.O. Box 187, Medicine Lodge, KS 67104-0187

Company to plug at: Hour: 3 p.m. Day: 15 Month: 6 Year: 19 93

Plugging proposal received from Jeff Sletto  
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4898', Perfs at 4754-61'  
1st plug sand back to 4700' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.  
hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 4:15 p.m. Day: 15 Month: 6 Year: 19 93.

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 4 sx cement on top of sand  
through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.  
hulls, released 8 5/8" wiper plug and pump 125 sx cement.

Maximum pressure 650 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3000' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(XXXXXX) observe this plugging.

DATE 6-24-93  
WV. NO. 37987

Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COM.  
JUN 18 1003  
6-18-93  
CONSERVATION DIVISION  
Wichita, Kansas