

To: 1 051672 6-14
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,472-0000
C SW SE, SEC. 11, T. 34 S, R. 20
660 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30972
Operator: Bishop Operating Company, Inc.
Name & Address: P.O. Box 1807
Hutchinson, KS 67504

Lease Name Petro 11 Well # 1
County Comanche
Well Total Depth 4850 157.62 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 670

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104-0187

Company to plug at: Hour: 10:10 a.m. Day: 14 Month: 6 Year: 19 93

Plugging proposal received from Jeff Sletto
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4850', Perfs at 4751-58'
1st plug sand back to 4700' and dump 4 sx cement on top of sand through bailer,
2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, and 125 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:55 a.m. Day: 14 Month: 6 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 4 sx cement on top of sand
through bailer,
2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls and 125 sx cement

Maximum pressure 700 psi and shut in 400 psi.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 4000' of 4 1/2" casing. JUN 18 1993
(If additional description is necessary, use BACK of this form.) 6-18-93

INVOICED

I (did / ~~did not~~) observe this plugging.

DATE 6-24-93
BY 37984

Signed Richard W. Lacy
(TECHNICIAN)