

To: 1051680  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

6-18

API NUMBER 15- 033-20,353-0000  
C SE NW, SEC. 11, T. 34 S, R. 20 W/EX

3300 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30972

Lease Name Beyler Well # 1-11

Operator: Bishop Operating Company, Inc.  
Name &  
Address P.O. Box 1807  
Hutchinson, KS 67504

County Comanche 171.24

Well Total Depth 5269 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 802

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 10:15 a.m. Day: 18 Month: 6 Year: 1993

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4854', PBTD 4868', Perfs at 4756-62'

1st plug sand back to 4700' and dump 5 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 18 Month: 6 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, released 8 5/8" wiper plug and pumped 125 sx cement

Maximum pressure 900 psi and shut in 600 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
6-23-93  
JUN 23 1993

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3600' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE: 6-24-93

Signed Richard W. Lacey  
(TECHNICIAN)

WV. NO. 37996