

To: 1 051685 6-23
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20,517-6000
C NE SW, SEC. 13, T. 34 S, R. 20 W/EX
1980 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30972
Operator: Bishop Operating Company Inc.
Name & Address P.O. Box 1807
Hutchinson, KS 67504

Lease Name Lemon Well # 15
County Comanche
Well Total Depth 4865 158.11 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 744

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 9 a.m. Day: 23 Month: 6 Year: 19 93

Plugging proposal received from Vernon Duntz
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4750' w/150 sx cement. Perfs at 4750-4865'
1st plug sand back to 4700' and dump 5 sx cement on top of sand through bailer,
2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 9:40 a.m. Day: 23 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4700' and dumped 5 sx cement on top
of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released
8 5/8" wiper plug and pumped 125 sx cement.
Maximum pressure 600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' fo 5 1/2" casing. STATE CORPORATION COMMISSION

INVOICED
I (did / x x x x x x x) observe this plugging.
DATE: 7-9-93
ENV. NO. 38079

RECEIVED
JUN 28 1993
6-28-93
Signed Richard W. Lacey
(TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas