

To: 1 051668
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-14

API NUMBER 15-033-20,501-0000

C SW NW, SEC. 13, T. 34 S, R. 20 WXB
3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30972
Operator: Bishop Operating Company, Inc.
Name &
Address P.O. Box 1807
Hutchinson, KS 67504

Lease Name Hackney Well # 2-13
County Comanche
Well Total Depth 4820 156.65 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 773

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104-0187

Company to plug at: Hour: 2:20 p.m. Day: 14 Month: 6 Year: 1993

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4819' w/175 sx cement, PBTD 4815', Perfs at 4770-76'

1st plug sand back to 4715' and dump 5 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:10 p.m. Day: 14 Month: 6 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 4715' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 900 psi and shut in 500 psi.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3400' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form)

JUN 18 1993
6-18-93
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(do not check next) observe this plugging.

DATE 6-24-93

Signed Richard M. Lacy
(TECHNICIAN)

WV. NO. 37985