



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

28 October 1981

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)  
15-033-20505-0000

Dear Sir:

Mr. Larry Friedel of Lawson Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Lawson, Donald C., Oil Producer  
Complete Address: 200 Douglas Bldg Broadway, Douglas, Wichita, Kansas 67202  
Lease Name: Barby - Harper Well No. A-1  
Location: 2150' FWL - 750 FSL Sec 31 Twp. 34S Rge. 21W (E) (W)  
County: Comanche Total Depth: 5710  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  DSA   
Other well as hereafter indicated: .. \_\_\_\_\_

Mr. Friedel was instructed to plug the well as follows:

The stone coral was topped at 1128'. There is 85' of 20" conductor pipe cemented from top to bottom. There is 833' of 8 3/8" surface casing cement circulated. 1st plug after circulating heavy mud for 10 min at 1050' with 50 bbl pumped to bottom 1050'. 2nd plug pushed rubber plug to 825' and pumped 40 bbl of cement on top of it. 3rd plug at 46' to 0' on solid bridge with 10 bbl of cement. Then 5 bbl cement in rat hole. Plugging accomplished by Allied Plugging out of Kiowa Kans.  
Very truly yours,

David Luthie  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION

NOV 2 1981  
11-2-81  
CONSERVATION DIVISION  
Wichita, Kansas