

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

NOV 26 1963

11-26-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts.
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. C. E. Richardson of Amerada Petroleum Corp. has this date requested permission to plug the following described well:

Mr. Richardson guarantees payment of the plugging fee.

Operator's full Name: Amerada Petroleum Corporation

Complete Address: Box 197, Great Bend, Kansas

Lease Name: Luella Mai Well No. # 1

Location: C NE SW Sec. 11 Twp. 34 Rge. 20 (E) (W) W

County Comanche Total Depth 6520 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Richardson was instructed to plug the well as follows:

532' of 8 5/8" surface pipe, cemented with 392 sacks.
Fill hole with drilling mud to 525', 1st cementing plug,
1/4 sack hulls, cement with 25 sacks. Fill hole with drill-
ing mud to 40', 2nd cementing plug, 1/4 sack hulls, cement
with 15 sacks to base cellar.

Very truly yours,

Archie Ewing
 Conservation Division Agent