



15-033-20125-0000

412

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 11-6-72 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Chism of Rains & Williamson Drlg has this date requested permission to plug the following described well:

Mr. Chism guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Co

Complete Address: 780 4th Natl Bldg Wichita, Ks

Lease Name: Woolfolk Ranch Well No. 1

Location: 2640" SNL & 1980" EWL Sec. 32 Twp. 34s Rge. 20 (E)(W) W

County: Comanche Total Depth 5510 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Chism was instructed to plug the well as follows:

647 ft 8 5/8 surface pipe cemented with 450 sacks. Pump

50 sacks cement to 600 ft. Mud to 40 ft, plug, 1/2 sack hulls,

15 sacks cement to surface. 2 sacks cement in rat hole.

Pumped by Globe Cementing Co. Great Bend, Ks

Very truly yours,

Russell B. Johnston
Conservation Division Agent