

LEASE NAME Harzman 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

SE NE NW Ft. from S Section Line

 Ft. from E Section Line

SEC. 33 TWP. 16 RGE. 11W (E) or (W)

COUNTY Barton

Date Well Completed 12/21/71

Plugging Commenced 7/6/2000

Plugging Completed 7/6/2000

LEASE OPERATOR Berexco, Inc.

ADDRESS Box 723 Hays, Kansas 67601

PHONE (785) 628 6101 OPERATORS LICENSE NO. 5363

Character of Well Oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on 7/6/2000 (date)

by Jay Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? if not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 3416

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	250	8 5/8		
	Casomg	0	3416	5 1/2		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.

Perf. 2 holes each at 1475', 790' 475'. Run 2 3/8 openend tubing to 2015'. Mix 180 sk. 60/40 poz, 10% gel, 400# hulls. Pull tbq. to 1023'. Circ. cement to surface up 5 1/2 with 80 sks 60/40 pos, 10% gel, 200# hulls. Pull tbq. Tie to 5 1/2 mix 25 sk 60/40 pos, 10% gel Squ Squeeze to 600#. Shut in 5 1/2 400#. Tie to 8 5/8 mix 15 sk. squeeze to 500#. Shut in at 200#. Well plugged 1:45 PM.

Name of Plugging Contractor Berexco, Inc. License No. 5363

Address Box 723 Hays, Kansas 67601

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

JUL 10 2000

STATE OF Kansas COUNTY OF Ellis, ss.

CONSERVATION DIVISION

Mr. Dennis Kirmer (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

NOTARY PUBLIC - State of Kansas
ROSEMARY SMITH
My Appt. Exp. 5-10-2003

(Signature) Dennis Kirmer

(Address) Box 723 Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 7 day of July, 2000

Rosemary Smith
Notary Public

My Commission Expires: 5-10-2003

DK