

STATE OF KANSAS
ATE CORPORATION COMMISSION
3 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 5009-23,875 00-00

LEASE NAME Brinson

WELL NUMBER 3

330 Ft. from S Section Line SWSE QTR.

1980 Ft. from E Section Line

SEC. 32 TWP. 16 RGE. 11W (E) or (W)

COUNTY Barton

Date Well Completed _____

Plugging Commenced 11-8-01

Plugging Completed 11-9-01

RECEIVED

NOV 15 2001

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR PETROLEUM TECHNOLOGIES, INC.

ADDRESS 801 W. 47th St. #412, Kansas City, MO. 64112

PHONE (816) 531-6904 OPERATORS LICENSE NO. 8653

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

This plugging proposal was approved on _____ (date)

by Patrick Staab (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 3367'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	358'	None
				5-1/2"	3366'	1954'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each side. Plugged off bottom with sand to 3270' and 5 sks. cement. Shot pipe @1954', pulled up to 1450', pumped 80 sks. cement and 300# hulls and circulated to surface. Layed rest of casing down, pumped 80 sks. cement and 200# hulls down 8-5/8". 60/40 pos. 10% gel.

Plugging Complete

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Petroleum Technologies, Inc.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 12th day of November, 2001

Irene Herzberg
Notary Public

My Commission Expires:

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-05

Form C-1
Revised 05-01