



15-033-20575-0000

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Tom Harmon of Alderson Drilling Co has this date requested permission to plug the following described well:

Operator's Full Name: K. R. M.

Complete Address: 817 17th St. Suite 820 Denver Colo. 80202

Lease Name: Christian Well No. 3-11

Location: C-SE-NE Sec. 11 Twp. 34 Rge. 20 (E) (W)

County: Cornwall Total Depth: 4830'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Harmon was instructed to plug the well as follows:

They cement circulated 684' of 8 5/8" surface casing. 1st plug at 1020' with 60 sby of cement. 2nd plug at 730' with 40 sby of cement. 3rd plug 40' to 0' on solid bridge with 10 sby of cement. Then circulated 10 sby cement in each the rat hole + mouse hole. The cement was pumped through drill pipe with hole full of heavy mud. The plugging was accomplished by

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1982

Paul A. Luthis
Conservation Division Agent

CONSERVATION DIVISION
Wichita, Kansas