

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21582-00-01
Spot: N2NENE Sec/Twnshp/Rge: 23-9S-24W
4950 feet from S Section Line, 660 feet from E Section Line
Lease Name: NICKLESON Well #: 23-2
County: GRAHAM Total Vertical Depth: 4045 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4045		425 SX
SURF	8.625	249		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/14/2014 12:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: SEAN FRIES Company: ALLIANCE WELL SERVICE INC. Phone: (308) 345-1597

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/500 # hulls.
CIBP at 3770' w/ junk stuck in hole below bridge plug. Cannot retrieve.
Perforations: 3837' - 3840', 3867' - 3869', 3925' and 3949'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/14/2014 3:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3760' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 2760' and pumped 100 sx cement. Pulled tubing to 1360' and pumped 40 sx cement. Good circulation of cement. Pulled tubing out and topped off w/50 sx cement. Tied on to backside and squeezed w/15 sx cement. Shut in pressure 300 psi.

GPS: 39.26155 -099.96120

Perfs:

Top	Bot	Thru	Comments
3949	3949		
3925	3925		
3867	3869		
3837	3840		

Received
KANSAS CORPORATION COMMISSION
AUG 27 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENT TICKET # 55399

Plugged through: TBG

District: 04

Signed _____

(Signature)

(TECHNICIAN)

9.2.14

CM

AUG 28 2014