

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22576-00-00
Spot: NESENE Sec/Twnshp/Rge: 5-7S-20W
3630 feet from S Section Line, 330 feet from E Section Line
Lease Name: LESAGE B Well #: 4
County: ROOKS Total Vertical Depth: 3730 feet

Operator License No.: 34903
Op Name: JASPAR CO.
Address: 1681 LIMESTONE ROAD SOUTH PO B
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3710		150 SX
SURF	8.625	262		180 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/13/2014 11:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: SHANE VEHIGE Company: JASPAR Phone: (785) 650-4910

Proposed Plugging Method: Alt II perforated 2 holes at 1640' cwc w/325 sx cement.
TOF at 3559'. Unknown junk in hole. Purchased lease, bad casing leaks at 1250' - 2800'.
Production perforations: 3433' - 3435'.
Ordered 350 sx 60/40 pozmix 4% gel cement w/800 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/13/2014 1:45 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3406'. Quality Oilwell Cementing pumped 75 sx cement w/350 # hulls. Pulled tubing to 2356' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 1331' and pumped 80 sx cement w/250 # hulls. Circulated cement. PTOH. Topped 4 1/2" casing off w/20 sx cement. Casing full. Hooked to backside and pumped 100 sx cement. Maximum pressure 100 psi. Shut in pressure 100 psi.

Perfs:

Top	Bot	Thru	Comments
3688	3691		
3613	3615		
3599	3600		
3576	3579		
3485	3487		
3450	3451		

Received
KANSAS CORPORATION COMMISSION
AUG 27 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

9.2.14

AUG 20 2014