

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-40157-00-00
Spot: NESWNWNW Sec/Twnshp/Rge: 1-35S-11E
4493 feet from S Section Line, 4887 feet from E Section Line
Lease Name: BECK Well #: 50
County: CHAUTAUQUA Total Vertical Depth: 1137 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	850		0 SX
SURF	10	15		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/04/2014 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Surface and production cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE
Date/Time Plugging Completed: 06/04/2014 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1000' gelled hole and spotted 20 sack plug. Pulled up to 700' and spotted 10 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 130 sacks of cement were used to plug this well.

Perfs:

RECEIVED

AUG 12 2014

KCC Chanute Dist. #3

DS

Received
KANSAS CORPORATION COMMISSION

AUG 18 2014


CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

9.2.14 OKM