

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22269-00-00
Spot: W2NESENW Sec/Twnshp/Rge: 26-10S-21W
3630 feet from S Section Line, 3020 feet from E Section Line
Lease Name: HOLZHAUER Well #: 1
County: GRAHAM Total Vertical Depth: 3804 feet

Operator License No.: 5616
Op Name: NOAH, CALVIN
Address: 329 N BIRCH
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3803		245 SX
SURF	8.625	249		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/13/2014 8:00 AM
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC
Proposal Rcvd. from: KITT NOAH Company: H2 PLAINS, LLC Phone: (316) 755-0058

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix4% gel cement w/1000 # hulls.
Perforations: 3440' - 3441', 3482' - 3485', 3517' - 3519', 3527' - 3529', 3767' - 3769', 3784' - 3785'.
5 1/2" casing has 420 sx cement to surface.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/13/2014 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3667' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2667' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 1667' and pumped 125 sx cement. Good circulation of cement. Pulled tubing out and topped off w/35 sx cement full. Tied on to backside and squeezed w/25 sx cement full.

GPS: 39.15710 -099.63456

Perfs:

Top	Bot	Thru	Comments
3784	3785		
3767	3769		
3527	3529		
3517	3519		
3482	3485		
3440	3441		


Received
KANSAS CORPORATION COMMISSION
AUG 27 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENT TICKET # 55469

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

9.2.14 CKM

AUG 21 2014