

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22453-00-00
Spot: N2N2SE Sec/Twnshp/Rge: 1-10S-22W
2310 feet from S Section Line, 1320 feet from E Section Line
Lease Name: BIDEN Well #: 2
County: GRAHAM Total Vertical Depth: 3900 feet

Operator License No.: 5616

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3902		135 SX
SURF	8.625	257		200 SX

Op Name: NOAH, CALVIN

Address: 329 N BIRCH
VALLEY CENTER, KS 67147

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/12/2014 12:00 PM

Plug Co. License No.: 33645

Plug Co. Name: H2 PLAINS, LLC

Proposal Rcvd. from: KITT NOAH

Company: H2 PLAINS, LLC

Phone: (316) 755-0058

Proposed Alt II perforations at 1801' w/450 sx cement.
Plugging Perforations at 3599' - 3600', 3559' - 3560', 3634' - 3635', 3643' - 3644', 3760' - 3761', 3736' - 3737'.
Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/1000 # hulls and 12 sx gel.

Plugging Proposal Received By: MARVIN MILLS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 08/12/2014 3:15 PM

KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3554' and pumped 3 sx gel followed by 75 sx cement w/100 # hulls. Pulled tubing to 2654' and pumped 100 sx cement w/150 # hulls. Pulled tubing to 1395' and pumped 75 sx cement w/200 # hulls. Good circulation of cement. Pulled tubing. Topped off w/25 sx cement full. Tied on to backside and squeezed w/5 sx cement full.

GPS: 39.21138 -099.72131

Perfs:


Top	Bot	Thru	Comments
3760	3761		
3736	3737		
3643	3644		
3634	3635		
3599	3600		
3559	3560		

Remarks: ALLIED CEMENT TICKET # 55468

Plugged through: TBG

District: 04

Received Signed
KANSAS CORPORATION COMMISSION


(TECHNICIAN)

CM

AUG 25 2014

9.2.14 ckm

Form CP-2/3

AUG 13 2014

CONSERVATION DIVISION
WICHITA, KS