

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21000-00-00
Spot: NWNW Sec/Twnshp/Rge: 24-9S-23W
4620 feet from S Section Line, 4620 feet from E Section Line
Lease Name: NINEMIRE Well #: 3
County: GRAHAM Total Vertical Depth: 1954 feet

Operator License No.: 6861
Op Name: RON'S OIL OPERATIONS INC
Address: 1889 200TH AVE
PENOKEE, KS 67659

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1953		475 SX
SURF	8.625	126		120 SX

Well Type: SWD UIC Docket No: D19370.0 Date/Time to Plug: 08/14/2014 8:00 AM
Plug Co. License No.: 34115 Plug Co. Name: SCHIPPERS OILFIELD SERVICES, LLC
Proposal Rcvd. from: RONALD NICKELSON Company: POE Phone: (785) 421-2315

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Shot perforations at 1200'.
4 1/2" production casing cemented to surface w/475 sx cement.
Perforations: 1640' - 1690'

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/14/2014 10:45 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 1630' and pumped 150 sx cement w/150 # hulls. Good circulation of cement.
Pulled tubing out and topped off w/15 sx cement full. Checked backside and filled with 10 sx cement full.
GPS: 39.26110 -099.84515


Perfs:

Received
KANSAS CORPORATION COMMISSION
AUG 27 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: GLOBAL CEMENT TICKET # 1422

Plugged through: TBG

District: 04

Signed 
(TECHNICIAN) CM
cc: UIC ✓
9.2.14 ckm

AUG 28 2014