

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-24519-00-00
Spot: S2NESESE Sec/Twnshp/Rge: 29-30S-8E
880 feet from S Section Line, 330 feet from E Section Line
Lease Name: CLARKE D 3008 Well #: 1-29
County: COWLEY Total Vertical Depth: 3464 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2830		
COND	20	40		10 SX
	II 7	3459		655 SX
PROD	7	3459		655 SX
SURF	9.625	556		325 SX
	T1 2.875	2366		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/18/2014 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: GEORGE RAYL Company: GRESSEL OILFIELD SERVICE Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS/ CIBP @ 2225 W/ 5 SXS, PULL PIPE CIRC. 600'-0' 60/44 POZMIX

Plugging Proposal Received By: JEFF KLOCK WitnessType: NONE
Date/Time Plugging Completed: 07/21/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2221', DUM BAILED 5 SXS CEMENTON TOP. RIH W/TBG @ 2150', GRESSEL OILFIELD LOADED HOLE W/33 BBL FLUID, & CIRCULATED ROTARY MUD TO SURFACE. RIH ON WIRELINE CUT CASING @ 1116', LAYED DOWN 26 JOINTS 7" CASING. RIH W/TBG @ 600', GRESSEL OILFIELD MIXED & PUMPED 275 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 7-21-2014, 8:15 PM.

Perfs:

Top	Bot	Thru	Comments
2901	2904		CSG
2874	2894		CSG
2271	2278		CSG

Received
KANSAS CORPORATION COMMISSION

AUG 18 2014

Remarks: CEMENT TICKET #42852.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 02

Signed

Duane Krueger
9.2.14 (TECHNICIAN)
okm

JK