

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-049-22333-00-00  
Spot: NWSESESW Sec/Twnshp/Rge: 11-31S-10E  
415 feet from S Section Line, 2975 feet from E Section Line  
Lease Name: SWARTZ/GLASSCOCK Well #: 7  
County: ELK Total Vertical Depth: 2372 feet

Operator License No.: 3359  
Op Name: T & R OIL COMPANY, A GENERAL PA  
Address: PO BOX 92  
MOLINE, KS 67353

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2371		235 SX
SURF	8.625	40		10 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/27/2014 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: ROGER PATTESON Company: \_\_\_\_\_ Phone: (620) 647-3352

Proposed Plugging Method: Place 20 sacks of cement at 1800 feet (drilled on junk iron for 5 1/2 hours without making any hole). Place 10 sacks of cement midway up hole, then cement to the top 500 feet.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/28/2014 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1700' gelled hole and spotted 20 sack plug. Pulled up to 1000' and spotted 10 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 85 sacks of cement were used to plug this well.

Perfs:


Top	Bot	Thru	Comments
2268	2269		
RECEIVED AUG 12 2014 KCC Chanute Dist. #3 DS Received KANSAS CORPORATION COMMISSION			

Remarks:

Plugged through: TBG

District: 03

Signed



9.2.14 *ckm*

(TECHNICIAN)

AUG 18 2014  
CONSERVATION DIVISION  
WICHITA, KS