

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21926-00-00
Spot: SWSESESW Sec/Twnshp/Rge: 10-16S-16W
264 feet from S Section Line, 2265 feet from W Section Line
Lease Name: LEGLEITER ET AL Well #: 1-10
County: RUSH Total Vertical Depth: 3644 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3416		WITH 3 SX CMT
PROD	5.5	3641	1505	WITH 175 SX CMT
SURF	8.625	1069		WITH 370 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/28/2014 2:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 3420' WITH 2 SX CMT. PLUG AT 1100' WITH 10 SX GEL & 50 SX CMT. PLUG AT 450' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS Witness Type: NONE
Date/Time Plugging Completed: 07/28/2014 3:30 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

CIBP @ 3416' WITH 3 SX CMT. 1ST PLUG AT 1108' WITH 50 SX CMT & 10 SX GEL. 2ND PLUG AT 456' WITH 40 SX CMT. 3RD PLUG AT 65' WITH 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3470	3476		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 05 2014

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed: Nathan Willis
(TECHNICIAN)

8-18-14 ckm

RECEIVED
JUL 29 2014
KCC DODGE CITY

Form CP-2/3