

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21935-00-00
Spot: NENE Sec/Twnshp/Rge: 28-33S-6W
660 feet from N Section Line, 660 feet from E Section Line
Lease Name: HARMON 3306 Well #: 2-28
County: HARPER Total Vertical Depth: 5108 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4840		
CIBP		4905		
COND		90		6 SX
PROD	5.5	5108	2200	326 SX
SURF	9.625	700		430 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/09/2014 12:00 PM
Plug Co. License No.: 34982 Plug Co. Name: TITAN WELL SERVICE, LLC
Proposal Rcvd. from: CODY Company: TITAN WELL SERVICE Phone: _____

Proposed Plugging Method: CIBP 4400 & 5 SKS. 50 SXS @ 1050, 50 SXS @ 750', CIRC 300'-0'.

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 07/09/2014 5:15 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 4400' & CAPPED WITH 5 SXS CEMENT. RECOVERED 2200' OF 5 1/2". PULLED & LAYED DOWN 5 1/2" CASING. RAN TUBING TO 1050' & SPOTTED 50 SXS CEMENT. PULLED TUBING TO 750' AND SPOTTED 35 SXS CEMENT. TAGGED CEMENT AT 625'. PULLED TUBING TO 300' & CIRC CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4914	4917		
4874	4882		
4447	4465		

KCC WICHITA
JUL 22 2014
RECEIVED

Remarks: COPELAND ACID & CEMENT #40891 COMMON

Plugged through: TBG

District: 02

Signed _____
8-18-14 ckm (TECHNICIAN)