

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-21762-01-00  
Spot: NWNEENE Sec/Twnshp/Rge: 10-21S-24W  
202 feet from N Section Line, 365 feet from E Section Line  
Lease Name: FRUSHER Well #: 1-10H  
County: HODGEMAN Total Vertical Depth: 4744 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4420		WITH 30 SX CMT
COND	20	113		WITH 15 SX GROUT
	L1 4.5	8797		WITH 450 SX CMT
PROD	7	4744	1399	WITH 200 SX CMT
SURF	9.625	749		WITH 440 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/28/2014 11:00 AM  
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.  
Proposal Rcvd. from: MATT BLOSE Company: SANDRIDGE EXPLORATION Phone: (405) 429-5500

Proposed Plugging Method: SET CIBP @ 4650' WITH 30 SX CMT. PLUG AT 1340' WITH 10 SX GEL & 50 SX CMT. PLUG AT 760' WITH 50 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 07/28/2014 7:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CIBP @ 4420' WITH 30 SX CMT. 1ST PLUG AT 1340' WITH 10 SX GEL & 50 SX CMT.  
2ND PLUG AT 760' WITH 60 SX CMT. 3RD PLUG AT 60' WITH 110 SX CMT.

Perfs:

Top	Bot	Thru	Comments
8289	8695		
7783	8189		
7278	7684		
6772	7178		
6267	6673		
5761	6167		
5256	5662		
4750	5156		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND CEMENTING. TMD = 8817'

Plugged through: TBG

Interval Billed 4073'

Received  
KANSAS CORPORATION COMMISSION

AUG 15 2014

CONSERVATION DIVISION  
WICHITA, KS

District: 01

RECEIVED

AUG - 8 2014

KCC DODGE CITY

Signed

*Michael J. Maier*

(TECHNICIAN)

8-18-14 ckm