

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-21017-00-01
Spot: E2E2NWSW Sec/Twnshp/Rge: 6-21S-33W
1980 feet from S Section Line, 4153 feet from E Section Line
Lease Name: CAMPBELL 2133 Well #: 1-6
County: FINNEY Total Vertical Depth: 4850 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4396		WITH 2 SX CMT
CIBP		4660		
DVT		1826		WITH 450 SX CMT
PROD	4.5	4835	0	WITH 450 SX CMT
SURF	8.625	440		WITH 230 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/29/2014 9:00 AM
Plug Co. License No.: 34982 Plug Co. Name: TITAN WELL SERVICE, LLC
Proposal Rcvd. from: ANTHONY Company: TITAN WELL SERVICE, LLC Phone: (405) 828-4225

Proposed Plugging Method: CIBP @ 4400'+/- WITH 2 SX CMT. RUN TBG TO 2000' +/- & FILL 4 1/2" CASING CMT. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 07/29/2014 6:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4396' WITH 2 SX CMT. RUN TBG TO 2000' & CIRCULATE CMT TO SURFACE. TOOH WITH TBG & TOP OFF. TOTAL CMT 180 SX. ATTEMPT TO PUMP DOWN ANNULUS. COULD NOT AT 500#. FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
4734	4757		
4562	4651		
4441	4757		

Received
KANSAS CORPORATION COMMISSION

AUG 15 2014

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG


District: 01

RECEIVED

AUG - 8 2014

KCC DODGE CITY

Signed



(TECHNICIAN)

8-18-14 ckm

