

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02032-00-00
Spot: NESESW Sec/Twnshp/Rge: 25-19S-6W
990 feet from S Section Line, 2970 feet from E Section Line
Lease Name: ANDERSON B Well #: 1
County: RICE Total Vertical Depth: 3386 feet

Operator License No.: 5172
Op Name: SCHULZ OIL & GAS, INC.
Address: 114 S MAIN PO BOX 515
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	7	3065		
PROD	7	3338	450	70 SX
SURF	10.75	150		80 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/01/2014 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 07/02/2014 11:15 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, TAG BOTTOM @ 3045'-CIBP HAD PREVIOUSLY BEEN CEMENTED. PERFORATE AT 2230' AND 900'. RUN TUBING TO 2230', AND PUMP 50 SX'S CEMENT WITH 3% CC. PULL TUBING TO 900' AND PUMP 50 SX'S. LET SET AWHILE, TAG CEMENT 2 525'. CUT CASING OFF AT 450' AND PUMP 50 SX'S PULL CASING OUT. RUN TUBING BACK INTO 250' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3338	3386	OH	

Remarks: 60-40 POZ, 4% GEL. QUALITY WELL SERVICE #6183.

KCC WICHITA

JUL 25 2014

Plugged through: TBG

RECEIVED

District: 02

Signed Virgil Clothier
(TECHNICIAN)

8-18-14 ccm