

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02041-00-00
Spot: SENWSWNW Sec/Twnshp/Rge: 25-19S-6W
3328 feet from S Section Line, 4664 feet from E Section Line
Lease Name: MATTSON Well #: 2
County: RICE Total Vertical Depth: 3367 feet

Operator License No.: 5172
Op Name: SCHULZ OIL & GAS, INC.
Address: 114 S MAIN PO BOX 515
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3330	620	150 SX
SURF	8.625	154		80 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/07/2014 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3409

Proposed Plugging Method: PER KCC RULES & REGS. IN 1973, WELL WAS PLUGGED BACK TO 3301' WITH ROCK AND CEMENT, AND AN ATTEMPT TO CEMENT A HOLE IN CASING AT 1670' WITH 100 SX'S CEMENT WAS UNSUCCESSFUL. WHEN CLEANING WELL OUT, TOOLS WERE GOING OUTSIDE OF CASING AT 1652'. THIS WELL WAS DENITED TA STATUS DUE TO HFLD, AND JUNK- OBSTRUCTION IN CASING.

Plugging Proposal Received By: JEFF KLOCK WitnessType: NONE
Date/Time Plugging Completed: 07/07/2014 12:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, RUN IN TUBING WITH NOTCHED COLLAR ON END AND STACKED OUT AT 850'. TRIED TURNING ON TO GO DEEPER WITH NO SUCCESS. PUMPED 35 SX'S CEMENT AT 850'. CUT CASING @ 620' AND PULLED OUT OF HOLE. RUN IN TUBING TO 500' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 250' AND CIRCUALTE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3330	3367	OH	

Remarks: QUALITY WELL CEMENT TICKET #6209. DENIED TA

Plugged through: TBG

KCC WICHITA

JUL 25 2014

RECEIVED

District: 02

Signed Virgil Clothier
(TECHNICIAN)
8.18.14 ckm

JK