

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22172-00-00
Spot: N2NWNW Sec/Twnshp/Rge: 24-19S-6W
4950 feet from S Section Line, 4620 feet from E Section Line
Lease Name: NEEL B Well #: 1
County: RICE Total Vertical Depth: 3525 feet

Operator License No.: 5172
Op Name: SCHULZ OIL & GAS, INC.
Address: 114 S MAIN PO BOX 515
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3375		
PROD	5.5	3523	1835	125 SX
SURF	8.625	259		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/09/2014 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3409

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: HUNTER CLARK WitnessType: PARTIAL
Date/Time Plugging Completed: 07/12/2014 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CHECK BOTTOM, RUN SANDLINE TO 3450'. SAND PERFS TO 3300' AND CAP WITH 5 SX'S CEMENT. CUT CASING OFF AT 1835' AND PULL TO 900' AND PUMP 35 SXS. PULL CASING TO 600' AND PUMP 35 SXS. PULL CASING UP TO 300'. COME BACK ON 7-11-14 AND ATTEMPTED TO TAG, COULD NOT. RUN CASING BACK IN TO 900' AND PUMPED 35 MORE SXS WITH 100#S COTTON HULLS & 2 % CC. PULL CASING UP TO 600'. LET SET FOR ABOUT 2 HOURS AND TAGGED CEMENT AT 687'. PUMPED 35 MORE SXS AT 600'. PULL CASING TO 300' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT. COME BACK ON 7-12-14 AND TAG CEMENT AT 687' - PUMPED 35 MORE SXS WITH 150# COTTON HULLS -- LET SET FOR 2 HOURS AND TAGGED AT 210'. CIRCULATE 70 SX'S CEMENT TO SURFACE AND TOP OFF WITH 35 SX'S.

Perfs:

Top	Bot	Thru	Comments
3360			CSG

Remarks: QUALITY CEMENT #6005

Plugged through: CSG

KCC WICHITA

JUL 25 2014

RECEIVED

District: 02

Signed Virgil Clothier
8-18-14 ccm (TECHNICIAN)