

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-30166-00-01  
Spot: W2NWSWNW Sec/Twnshp/Rge: 17-10S-19W  
3604 feet from S Section Line, 5104 feet from E Section Line  
Lease Name: DICK Well #: 2  
County: ROOKS Total Vertical Depth: 3959 feet

Operator License No.: 32278  
Op Name: TENGASCO, INC.  
Address: 1327 NOOSE RD PO BOX 458  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3951		150 SX
SURF	8.625	195		140 SX

Well Type: SWD UIC Docket No: D19247.0 Date/Time to Plug: 07/28/2014 8:30 AM  
Plug Co. License No.: 32332 Plug Co. Name: FISCHER WELL SERVICE, INC.  
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed DV Tool at 1639 w/450 sx cement.  
Plugging Open Hole completion: 3951' - 3959'.  
Method: Ran tubing to plug. Failed MIT.  
  
Ordered 380 sx 60/40 pozmix 4% gel cement w/600 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/28/2014 12:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3600'. Quality Oilwell Cementing pumped 100 sx cement w/300 # hulls. Pulled tubing to 2550' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 1204' and pumped 45 sx cement. Cement circulated. PTOH. Topped 4 1/2" casing w/20 sx cement. Hooked to 8 5/8" surface pipe and pumped 50 sx cement. Maximum pressure 150 psi. Shut in pressure 100 psi.

Perfs:

Top	Bot	Thru	Comments
3951	3959		

KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING

AUG 07 2014

Plugged through: TBG

RECEIVED

District: 04

Signed Richard Williams  
CC: UIG (TECHNICIAN) CM

8.18.14 CKM

JUL 29 2014