

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21556-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 2-18S-13W
3630 feet from S Section Line, 2310 feet from E Section Line
Lease Name: AKERS Well #: 2
County: BARTON Total Vertical Depth: 3320 feet

Operator License No.: 30886
Op Name: THOMAS, JOHN R. DBA VAMCO OPER
Address: 265 AVENUE K
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3317		150 SX
SURF	8.625	426		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/24/2014 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 12 sx gel and 500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/24/2014 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 1400', 715' and 300'. Ran tubing to 3060' and pumped 12 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1491' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 693'. Circulated cement to surface on surface pipe and casing w/165 sx cement. Pulled tubing and topped off with 30 sx cement w/3% cc.

GPS: 38.51857 -098.72805

Remarks: QUALITY WELL SERVICE

Plugged through: CSG

KCC WICHITA
AUG 07 2014
RECEIVED

District: 04

Signed Bruce Rodie
8-18-14 CCM(TECHNICIAN)

CM

JUL 30 2014